

SECTION 02000 - EARTHWORK

PART 1 - GENERAL

1.1 WORK INCLUDED IN THIS SECTION

- A. The WORK of this Section includes all earthwork required for construction of the WORK. Such earthwork shall include the loosening, removing, loading, transporting, depositing, and compacting in its final location of all materials wet and dry, as required for the purpose of completing the WORK.
- B. Fill material is defined as material used to raise the level of a portion of the site to the line and grade indicated. Backfill material is defined as material used to refill an excavation.

1.2 REFERENCE SPECIFICATIONS

- A. Except as otherwise indicated in this Section of the Specifications, the CONTRACTOR shall comply with the latest edition of the Standard Specifications for Public Works Construction (SSPWC) together with the latest edition of the Regional Supplement Amendments.

1.3 REGULATORY REQUIREMENTS

- A. The WORK of this Section shall comply with current versions and revisions, of the following:
 - 1. Construction Safety Orders, Division of Industrial Safety, State of California.
 - 2. California Department of Transportation Traffic Manual.

1.4 SHOP DRAWINGS AND SAMPLES

- A. The following shall be submitted in compliance with Section 01300:
 - 1. The CONTRACTOR shall comply with the provisions for "Shoring and Bracing Drawings" in Section 6705 of the California Labor Code.
 - 2. The CONTRACTOR, prior to beginning any trench or structure excavation 5 feet deep or over shall submit to the DISTRICT and shall be in possession of the DISTRICT's written acceptance of the CONTRACTOR's detailed plan showing design of all shoring, bracing, sloping of the sides of excavation, or other provisions for worker protection against the hazard of caving ground during the excavation of such trenches or structure excavation. If such plan varies from the shoring system established in the Construction Safety Orders of the State of California, such alternative system plans shall be prepared by a civil or structural engineer licensed in the State of California.

3. Copies of relevant and necessary excavation permits.
4. Samples of imported material. Samples shall be submitted in accordance with SSPWC, Subsection 306-1.3.5.
5. Such other samples of materials as the ENGINEER may require.

1.6 SOIL TESTING

- A. All soil testing shall be done in accordance with SSPWC, Section 211, and by a testing laboratory of the DISTRICT's choice. Cost shall be borne by DISTRICT if CONTRACTOR is hired by DISTRICT. Cost shall be borne by DEVELOPER if CONTRACTOR is hired by DEVELOPER.
- B. Where soil material is required to be compacted to a percentage of maximum density, the maximum density shall be determined in accordance with the requirements of SSPWC, Subsection 211-2. In case the tests of the fill or backfill show non-compliance with the required density, the CONTRACTOR shall accomplish such remedy as may be required to ensure compliance. Subsequent testing to show compliance shall be by a testing laboratory selected by the DISTRICT and shall be at the CONTRACTOR's expense.

PART 2 - PRODUCTS

2.1 FILL AND BACKFILL MATERIALS

- A. Fill and backfill material shall consist of select material obtained from the excavation, imported material, granular bedding material, or unclassified material.
- B. The CONTRACTOR shall import at his expense materials in excess of the approved material obtained from excavation as required to complete the fill, backfill, and grading WORK as indicated.
- C. Select material shall consist of primarily granular material encountered in the excavation which is free of vegetation, organic matter, debris, rocks larger than 3 inches in diameter and other unsuitable material, and shall have an expansion index less than 30 (less than 20 for footings and floor slabs) as determined by UBC Standard No. 29-2, plasticity index of 10 or less, a liquid limit of 30 or less and shall be approved as select material by the ENGINEER.
- D. Imported material shall conform to the same specifications as select material defined above. In addition, the imported materials shall have a minimum sand equivalent of 30 as determined by California Test Method No. 217.
- E. Imported material placed in areas to be planted shall be able to support normal plant growth. Obtain approval of the ENGINEER prior to transporting imported material.

- F. Bedding material, defined as that material 6 inches below bottom of pipe, supporting, surrounding and extending to 1 foot above the top of a pipe, shall be in accordance with SSPWC, Subsection 306-1.2.1.
- G. Unclassified material shall conform to SSPWC, Subsection 300-4.

2.2 ROCK PRODUCTS

- A. Rock products, consisting of crushed rock, rock dust, gravel, sand, and stone for riprap shall be clean, hard, sound, durable, uniform in quality and free of disintegrating material, organic matter, oil alkali, or other deleterious substance, and shall, unless otherwise specified, conform with requirements of SSPWC, Subsection 200-1.

2.3 UNTREATED BASE MATERIALS

- A. Untreated base materials shall conform with the requirements of SSPWC, Subsection 200-2.
- B. Materials for use as untreated base or subbase shall be as specified by the DISTRICT.

2.4 TOPSOIL

- A. Topsoil shall be designated as Class A (imported), Class B (select), or Class C (unclassified), and shall conform with the requirements of SSPWC, Subsection 212-1.1. The ENGINEER shall determine the suitability of topsoil prior to use.

PART 3 - EXECUTION

3.1 GENERAL

- A. The CONTRACTOR shall perform earthwork as necessary to complete the WORK as shown on the Contract Drawings and specified herein.
- B. The CONTRACTOR shall take the necessary precautionary measures to prevent dust or other nuisances which might be created by reason of its activities. The necessary precautionary measures shall conform to the requirements of SSPWC, Subsection 7-8. The requirements specified in Subsection 7-8 shall be extended to include paved surfaces.
- C. All types of earthwork, including trench, structural and general excavation, fill, backfill and compaction, shall conform to applicable requirements of SSPWC, Section 300, and to the requirements specified herein.

3.2 SITE PREPARATION

- A. Areas to be excavated, filled, graded, and to be occupied by permanent construction or embankments shall be prepared by clearing and grubbing.

Clearing and grubbing shall conform to the applicable requirements of SSPWC, Subsection 300-1.

3.3 EXCAVATION

A. GENERAL

1. Except when specifically provided to the contrary, excavation shall include the removal of all materials of whatever nature encountered, including all obstructions of any nature that would interfere with the proper execution and completion of the work. Unless otherwise directed, the removal of said materials shall conform to the lines and grades shown.
2. Unless otherwise provided, the entire construction site shall be stripped of all vegetation and debris, and such material shall be removed from the site prior to performing any excavation or placing any fill.
3. The CONTRACTOR shall furnish, place, and maintain all supports and shoring that may be required for the sides of the excavations, and all pumping, ditching, or other measures for the removal or exclusion of water as required by Section 02140.
4. Excavations shall be sloped or otherwise supported in a safe manner in accordance with the rules, orders, and regulations of the Division of Industrial Safety and the State of California.

B. Unclassified Excavation

1. Unclassified excavation shall consist of all excavation, including roadways, unless separately designated.
2. Unsuitable material shall be excavated and disposed of in accordance with the requirements of SSPWC, Subsection 300-2.2.
3. Wet material, if unsatisfactory for the specified use on the project solely because of high moisture content, may be processed to reduce the moisture content, or may be required to be removed and replaced with suitable material in accordance with the requirements of SSPWC, Subsection 300-2.2.2.
4. The removal and disposal of slide and slipout material shall be in accordance with SSPWC, Subsection 300-2.4.
5. Excavation slopes shall be finished in conformance with the lines and grades shown, and in accordance with SSPWC, Subsection 300-2.5.
6. Surplus material shall be disposed of off-site, and in accordance with SSPWC, Subsection 300-2.6.

C. Structure Excavation

1. Structure excavation shall consist of the removal of material for construction of foundations for bridges, retaining walls, headwalls, culverts, buildings, or other structures, and shall be in accordance with SSPWC, Subsection 300-3.
2. Cofferdams for foundation construction shall be constructed in accordance with SSPWC, Subsection 300-3.2.
3. The treatment of foundation material shall be in accordance with SSPWC, Subsection 300-3.3.

D. Underground Conduit Excavation

1. Excavation for underground conduits shall be in accordance with SSPWC, Subsection 306-1.1 and the requirements contained herein.
2. Unless otherwise shown or ordered, excavation for pipelines and utilities shall be open-cut trenches.
3. The manner of bracing excavations shall be as set forth in rules, orders and regulations of the Division of Industrial Safety of the State of California, and in accordance with the requirements of SSPWC, Subsection 306-1.1.6.
4. The maximum amount of open trench permitted in any one location shall be 500 feet, or the length necessary to accommodate the amount of pipe installed in a single day, whichever is greater. All trenches shall be fully backfilled at the end of each day or, in lieu thereof, shall be covered by heavy steel plates adequately braced and capable of supporting vehicular traffic in those locations where it is impractical to backfill at the end of each day. The above requirements for backfilling or use of steel plate will be waived in cases where the trench is located further than 100 feet from any traveled roadway or occupied structure. In such cases, however, barricades and warning lights conforming to requirements set forth in the California Department of Transportation Traffic Manual shall be provided and maintained.
5. Where pipelines are to be installed in embankment fills, the fill shall be constructed to a level at least 18 inches above the top of the pipe before the trench is excavated.

E. OVER-EXCAVATION

1. Trenches shall be over-excavated beyond the depth shown when required by the ENGINEER. Such over-excavation shall be to the depth ordered. The trench shall then be backfilled to the grade of the bottom of the pipe.
2. All work specified in this Section shall be performed by the CONTRACTOR at no additional cost to the DISTRICT when the over-

excavation ordered by the ENGINEER is less than 1 foot below the limits shown.

3. When the over-excavation ordered by the ENGINEER is 1 foot or greater below the limits shown, additional payment will be made to the CONTRACTOR for that portion of the work which is located below said 1 foot distance.
4. Any over-excavation carried below the grade ordered or indicated shall be backfilled to the required grade with the specified material and compacted. Such work shall be performed by the CONTRACTOR at no additional cost to the DISTRICT.

F. Excavation in Lawn Areas

1. Where excavation occurs in lawn areas, the sod shall be carefully removed and stockpiled to preserve it for replacement.
2. Excavated material may be placed on the lawn; provided, that a drop cloth or other suitable method is employed to protect the lawn from damage.
3. The lawn shall not remain covered for more than 72 hours.
4. Immediately after completion of backfilling [and testing of the pipeline], the sod shall be replaced in a manner so as to restore the lawn as near as possible to its original condition.
5. CONTRACTOR shall provide new sod if removed sod has remained stockpiled for more than 72 hours.
6. The CONTRACTOR shall restore the lawn irrigation system removed or damaged due to excavation operations to a condition equal to the previous condition.

G. Excavation in Vicinity of Trees

1. Except where trees are shown to be removed, trees shall be protected from injury during construction operations. No tree roots over 2 inches in diameter shall be cut without written permission of the ENGINEER.
2. Trees shall be supported during excavation by means previously reviewed by the ENGINEER.

H. Rock Excavation

1. Rock Excavation shall include removal and disposal of the following
 - a. All boulders measuring $1/3$ of a cubic yard or more in volume

- b. All rock material in ledges, bedding deposits, and unstratified masses which cannot be removed without systematic drilling and blasting
 - c. Concrete or masonry structures which have been abandoned
 - d. Conglomerate deposits which are so firmly cemented that they possess the characteristics of solid rock and which cannot be removed without systematic drilling and blasting
2. Said rock excavation shall be performed by the CONTRACTOR; provided that, should the quantity of rock excavation be affected by any change in the scope of the WORK, an appropriate adjustment of the contract price will be made.

3.4 FILL AND BACKFILL

A. General

1. Fill and Backfill shall be placed in accordance with the applicable provisions of SSPWC, Section 300, and the requirements stated herein.
2. Backfill shall not be dropped directly upon any structure or pipe.
3. Backfill shall not be placed around or upon any structure until the concrete has been properly cured in accordance with the specifications and has attained sufficient strength to withstand the loads imposed.
4. Backfill around water retaining structure shall not be placed until the structures have been tested, and the structures shall be full of water while backfill is being placed.
5. Except for drainrock materials being placed in over-excavated areas or trenches, backfill shall not be placed until all water is removed from the excavation.

B. Placing and Spreading of Materials

1. Materials shall be placed and spread evenly in layers.
2. During the spreading, each layer shall be thoroughly mixed as necessary to promote uniformity of materials in each layer.
3. Where the material moisture content is below the optimum moisture content, water shall be added and mixed before it is placed in the trench for backfill.
4. Where the material moisture content is too high to permit the specified degree of compaction, the material shall be dried until the moisture content is satisfactory.

5. When compaction is achieved using mechanical equipment the layers shall be evenly spread so that when compacted, each layer shall not exceed 8 inches in thickness.

C. Compaction Requirements

1. Compaction tests shall be performed in accordance with SSPWC, Subsection 211-2.
2. The relative compaction of fill, backfill, and base material shall be in accordance with SSPWC, Section 300, with the following exceptions:
 - a. Subgrade where trench has been over-excavated 95%
 - b. One foot layer of crushed aggregate backfill in over-excavated trench. Where trench is over-excavated more than 2 feet, minimum of 2 layers shall be compacted. 95%
 - c. Pipe zone for flexible and rigid pipe: 95%
 - d. Fill beneath structures, including water containing structures: 95%

D. Unclassified Fill

1. All fill shall be of unclassified material unless separately designated. Construction of unclassified fill, including preparing the area on which fill is to be placed, and the depositing, conditioning, and compacting of fill material shall be in accordance with SSPWC, Subsection 300-4.

E. Structure Backfill

1. Backfill at structure shall be select material placed in accordance with SSPWC, Subsections 300-3.5 and 300-4.5.

F. Underground Conduit Backfill

1. Bedding around pipe shall be bedding material placed in accordance with the requirements of SSPWC, Subsection 306-1.2.
2. Backfill above shall be considered as starting 1 foot above the pipe or conduit, or at the subgrade for cast-in-place structures such as manholes, transition structures, junction structures, vaults, and valve boxes.
3. Backfill at underground conduits shall be select material placed and densified according to SSPWC, Subsection 306-1.3.

3.5 PREPARATION OF SUBGRADE UNDER IMPROVEMENT

- A. The preparation of subgrade for pavement, curbs and gutters, driveways, sidewalks and other roadway structures shall be in accordance with SSPWC, Subsection 301-1.

3.6 UNTREATED BASE

- A. Spreading and Compacting
 - 1. Aggregate base material shall be spread and compacted in accordance with SSPWC, Subsection 301-2.

END OF SECTION